KOLAR DIVISION.

Dated 6th September 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 1st October 1929, for constructing a Witness shed to the Munsiff's Court at Kolar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and fifty in cash, or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Witness shed to the Munsiff's Court at Kolar in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in exess or lower than the estimate will not be accepted.

Abstract estimate for constructing a Witness shed at Kolar.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavating foundation and filling in basement.	C.yds.		34	
2	Chunnam coucrete with burnt stone jelly	C.ft.		307	
3	Burnt stone in mortar ...	,,		772	
4	Burnt brick in mortar ...	,,		396	
5	Burnt stone slabs 4" to 6" dressed ...	S.ft.		120	
6	Providing stone benches nicely dressed with vertical srpports.	,,		149	
7	Teakwood wrought and put up ...	C.ft.		87	
8	Providing expanded metal of 2" mash with teakwood frame including chocolate painting.	S.ft.		363	
9	Teakwood door with pannelled shutters for $2\frac{1}{2}$ height $\times 4\frac{1}{4}$ expanded metal $1\frac{1}{2}$" mesh with hinges bolts, etc., complete, including painting.	,,		41	
10	Chunnam plastering ...	,,		10·06	
11	Cement pointing	Sqr.		1·80	
12	Roofing with 1st class Mangalore tiles 1" teak reepers.	,,		18·12	
13	Flooring with burnt stone slabs 3" thick dressed over 3" concrete bedding including cement pointing,	,,		5·42	
14	Wood oiling	,,		11·00	
15	Ridge tiles set in mortar	R.ft.		84	
16	Clearing site, etc. ...	Lump sum		Rs	
17	Mortar bands ...	R.ft.		231	
18	Eave board ornamental 9"×1" including .. painting.	,,		130	

Notification dated 16th September 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 1st October 1929, for Restoring Chowdadenahalli Tank Regd. No. 91—666 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred only in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Chowdadenahalli Tank Regd. No. 91—666 of Malur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenders stating that the work would be executed at a certain percentage of or lower than the estimate will not be accepted.

Abstract estimate for Restoring Chowdadenahalli Tank Regd. No.91—666 of Malur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork to bund watering and tamping from commencement to C. S. 11 as per original estimate.	C.yd.		3,568	
	Diverted portion of bund	,,		2,399	
2	Turfing to bund—from commencement to C. S. 11 as per original estimate.	,,		3,775	
	For diverted portion of bund ...	,,		990	
3	New stone work—from commencement to C. S. 11 as per original estimate.	,,		1,147	
	For diverted portion of bund as per statement attached.	,,		302	
4	Removing and resetting old stone work till 11 C. S.	,,		...	
5	Fixing grade stones with painting, etc., complete.	No.		25	
6	Fixing grade stones index stones with painting, etc., complete.	,,		25	
7	Register No. Stones do ...	,,		1	
8	Gauge stone do ...	,,		1	
9	B. M. stones do ...	,,		2	
10	Jungle clearing here and there ...	Lump sum		...	
	Sluice No. 1 R. L. 42·00.				
1	Earthwork cut opening the bund ...	C.yd.		62	
2	Refixing the same with	,,		62	
3	Surki concrete for foundation	C.ft.		310	
4	Burnt brick in surki mortar	,,		320	
5	Burnt stone slabs 4" to 6" thick	Sqrs.		272	
6	Plastering with surki mortar	,,		5·73	

No.	Details of work	Unit	Rate	Quantity	Cost
7	Providing wooden plug with rod and locking arrangement.	Lump sum		...	
8	Cutting holes in cross and orifice slabs lump sum.	No.		3	
	Sluice No. 2 as above No. 1 Sluice.				
	Waste weirs.				
1	Earthwork excavation for body wall and returns.	C.yd.		134	
2	Surki concrete for foundation	C.ft.		404	
3	Burnt brick in surki mortar	,,		1,221	
4	Burnt stone slabs 4" to 6" thick ...	Sq.ft.		480	
5	Plastering with surki mortar	Sqr.		15·51	
6	New stone for apron including lead of 2 to 3 miles.	C.yd.		113	

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Notice dated 12th September 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. of 23rd October 1929, for constructing Female Dispensary with out-houses at Sira. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. five hundred in cash or Government Promisery Notes as earnest money and be superscribed "Tender for constructing Female Dispensary with out-houses at Sira" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements quality of work, etc., and in all disputes of any kind the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump provisions are subject to modifications as per data worked out during execution. For individual items of work under lumpsum provisions the rates tendered for similar items of works will be paid and for other ilems, the rates as per schedule of rates will be paid at the descretion of the Executive Engineer.